

## SENARAI SKOP KERJA DAN HARGA (BQ)

NAMA BAHAGIAN/UNIT : HT TEAM

QUOTATION TO CARRY OUT RECTIFICATION WORKS FOR ACB TERASAKI AT CHILLER PLANT ROOM IRK AND SERVICING & MAINTENANCE OF LV INSTALLATIONS RECALIBRATION OF PROTECTION RELAYS AT INTERNATIONAL ISLAMIC UNIVERSITY MALAYSIA (IIUM), GOMBAK CAMPUS.

Item	Description	Quantity	Rate (RM)	Total (RM)
1	<p><b>ACB BREAKER</b></p> <p>To perform electrical testing and rectification for LV MSB :</p> <ul style="list-style-type: none"> <li>- To supply new copper busbar 2000Amp for ACB Terasaki including modification works</li> <li>- To do modification for main copper busbar incoming and outgoing supply from ACB</li> </ul>	1 lot		
2	<p><b>LV PANEL</b></p> <p>Servicing, maintenance and testing of ACB :</p> <ul style="list-style-type: none"> <li>- Insulation Resistance Test</li> <li>- Continuity Test / Ohm Test for ACB</li> <li>- General cleaning and lubrication for mechanism part</li> </ul>	1 lot		
3	<p>General inspection, servicing and cleaning of switchboard c/w checking and tightening bolts &amp; nuts at LV Panel. Cleaning room LV.</p>	1 lot		

4	General inspection, servicing and testing of Power Factor Correction Board (Capacitor Bank). retighten cable at Capacitor Bank MCCB, Contactor and testing by Measure Micro Farad and Current Value for Cap Bank and record.	1 lot		
<b>PROTECTION RELAYS</b>				
5	Testing and recalibration of Combined Over-current and Earth-fault protection relays	1 lot		
6	Provide competent person for ptw , switching (shut down and normalize)	1 lot		
<b>TOTAL</b>				

For any inquiries, kindly contact our person in charge En. Muhamad Khaldi Bin Zainal 013-3338416

CHARGEMAN B0/33KV DBSD

---

ACB CHILLER PLANT ROOM IRK

